


LOUVER SCHEDULE								
EQUIPMENT NO.	CFM	DESCRIPTION	TYPE	SIZE	MAX PRESSURE DROP (IN. WG)	COLOR	BASIS OF DESIGN	NOTES
LV-001	50,000	DRAINABLE BLADE LOUVER	WALL MOUNTED	180" X 96"	0.1"	GRAY	GREENHECK ESD-635X FLORIDA PRODUCT APPROVAL #: FL6876.4	SEE BELOW
<div>NOTES:</div> <div><div>1.</div><div>INSTALL ALUMINUM OR STAINLESS INSECT SCREEN WITH 300 SERIES STAINLESS STEEL SHEET METAL SCREWS. FASTENERS TO BE APPROXIMATELY 16" ON CENTER UNLESS OTHERWISE NOTED BY MANUFACTURER RECOMMENDATIONS.</div></div> <div><div>2.</div><div>TESTED IN ACCORDANCE WITH AMCA FOR WATER PENETRATION, AIR PERFORMANCE, AND WIND-DRIVEN RATINGS.</div></div> <div><div>3.</div><div>INSTALL PER MANUFACTURER INSTRUCTION AND IN ACCORDANCE WITH MIAMI DADE APPROVAL.</div></div>								



NOTE:

JAMB SIMILAR TO HEAD. LOUVER MUST BE INSTALLED PER MANUFACTURER'S INSTALLATION METHOD TO COMPLY WITH MIAMI DADE APPROVAL. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROPERLY INSTALL THE LOUVER PER THE MANUFACTURER'S DETAILS.

1 LOUVER DETAIL

NOT TO SCALE (NOTE 1)

NOTES:

1. SEE STRUCTURAL DRAWING FOR INFORMATION ON EXISTING GIRT MODIFICATIONS.

ISSUED FOR APPROVAL





ISOMER PROJECT GROUP
115 WELBORN ST, SUITE A
GREENVILLE, SC 29601
www.isomer.group

THIS DOCUMENT CONTAINS DATA THAT IS CONFIDENTIAL AND IT MAY NOT BE COPIED OR DISCLOSED, AND MAY BE USED BY THE CLIENT ONLY IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS INTENDED. ANY USE OF, OR RELIANCE ON, THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK.

WAREHOUSE EXPANSION
TELLUS PRODUCTS, LLC
37021 GATOR BLVD
BELLE GLADE, FL 33430

DOCUMENT TITLE

MECHANICAL
HVAC DRAWING
SCHEDULES AND GENERAL NOTES

A	14SEP23	ISSUED FOR APPROVAL	JRS	BDH	JNC
REV	DATE	REVISION & ISSUE HISTORY	DES	CHK	APP

PROJECT NO.	DRAWING NO.	REV.
TEL2305	ME-HVAC-0006	A