

- NOTES:
1. CONTRACTOR TO USE 4/0 BARE COPPER GROUND WIRE UNLESS OTHERWISE NOTED.
 2. CONTRACTOR TO INSTALL GROUND WIRE AT A MINIMUM OF 18" BELOW FINISHED GRADE.
 3. CONTRACTOR TO TIE NEW GROUND WIRE INTO EXISTING BUILDING GROUND RING.
 4. CONTRACTOR TO TIE GROUND RING INTO REBAR.

LIGHTING LEGEND

- BOLTED CONNECTION
- EXOTHERMIC CONNECTION
- GROUND WIRE
- ⊙ GROUND ROD
- ⦿ TEST WELL

WHPP-0001
480V PANEL BOARD

WHPP-0002
120/208V PANEL BOARD

WHX-0001
480-120/208V
XFMR

WAREHOUSE

OFFICE


STORAGE

TRUCKERS
ENTRANCE

THIS DOCUMENT CONTAINS DATA THAT IS CONFIDENTIAL AND IT MAY NOT BE COPIED OR DISCLOSED, AND MAY BE USED BY THE CLIENT ONLY IN THE CONTEXT AND FOR THE EXPRESS PURPOSE FOR WHICH IT WAS INTENDED. ANY USE OF, OR RELIANCE ON, THIS DOCUMENT BY ANY THIRD PARTY IS AT THAT PARTY'S SOLE RISK.

ISOMER PROJECT GROUP
115 WELBORN ST., SUITE A
GREENVILLE, SC 29601
www.isomer.group

REV	DATE	REVISION & ISSUE HISTORY	DES	CHK	APP
0	24AUG23	ISSUED FOR CONSTRUCTION	KCB	NRR	JNC



SCALE AS NOTED

telius
plant product planet

WAREHOUSE EXPANSION
TELLUS PRODUCTS, LLC.
37021 GATOR BLVD
BELLE GLADE, FL 33430



DOCUMENT TITLE
ELECTRICAL
GROUNDING PLAN

PROJECT NO.	DRAWING NO.	REV.
TEL2305	EL-PLN-0003	0